OFFICAL DOCUMENT

DO NOT REMOVE From Research Office

# Acoustic Characteristics of Roadway Surfaces

Final Report WA-RD 129.1

September 1987



# Washington State Department of Transportation

Duane Berentson, Secretary A.D. Andreas, Deputy Secretary James P. Toohey, Assistant Secretary for Planning, Research and Public Transportation

# Washington State Transportation Commission Research Committee

William O. Kamos, Chair Richard Ocabashian, Commissioner Jerry Overton Commissioner Leo B Sweeney, Commissioner

WSDOT Research Executive Committee

A.D. Andreas, Chair, Deputy Secretary for Transportation E.W. Ferguson, District 4 Administrator H. W. Parker, Assistant Secretary for Marine Transportation Robert C. Schuster, Assistant Secretary for Highways James P. Toohey, Assist. Sec. for Plan'g, Research & Public Transp.

#### WSDOT Research Technical Committees

Highway Operations and Development

Roland Cook, Chair, District 2 Administrator John Aspaas, District 4 Project Engineer William P. Carr, Associate Research Director John Conrad, District 1 District Operations Engineer Rich Dameil, District 3 Maintenance & Operations Engineer C. Sæwart Gloyd, Bridge/Structures Engineer Wayne Gruen, State Traffic Engineer Stan Moon, Location/Design Engineer Ed Schect, Construction Engineer - Paving Don Senn, District 2 Location/Construction Engineer Dick Shroti District 6 Maintenance Superintendent Ken Thomas. Operations Engineer, Bellingham Public Works Department George Tisatis: Structural Engineer, Washington State University

Materials and Product Evaluation

De Vanceney, Chair, State Construction Engineer Keith W. Anderson, Federal Program Manager Jim Buss, District 5 Construction Engineer Newton Jackson, Pavement/Soils Engineer Steve Kramer, Assistant Professor, Civil Engineering, U. of Washington Bob Kner, Bridge Operations Engineer Art Peters, Materials Engineer Bob Spratt District 2 Maintenance Engineer John Strada, Construction Engineer - Grading

Planning and Multimodal

Don Tranum, Chair, District 6 Administrator Ron Anderson, Manager, District 6 Management Services Ken Casavant, Professor, Washington State University King Cushman, Director, Pierce County Transit Development Kris Gupta, Manager, Transportation Data Office Kern Jacobson, District 1 Public Transportation & Planning Engineer Jerry Lenzi, Manager, Multi Model Branch Jim Stakey, Manager, Public Transportation Stephen Smith, Service Planning Manager, Ferry System, Colman Dock

#### WSDOT Research Implementation Committee Stan Moon, Chair, Location/Design Engineer

Jack E. Hanson, Location Engineer Dennis Ingham, Highway Maintenance Engineer Kern Jacobson, District 1 Public Transportation and Planning Engineer Bob Kner, Bridge Operations Engineer Art Peters, Materials Engineer Ed Schiect, Construction Engineer, Paving Gerald Smith, District 1, Assistant I-90 Construction Engineer Bob Spratt, District 2 Maintenance Engineer

WSDOT Research Office

John Doyle, Director William P. Carr, Associate Director Keith W. Anderson, Federal Program Manager Julie Leverson, Database Coordinator Ellen Loyer, Secretary

Carl Toney, Research Administrator

## WSDOT Research Lieisons

District 1 - Kern Jacobson, Public Transportation and Planning Engineer

District 2 - Don Senn, Location/Construction Engineer District 3 - Bob George, Assistant Location Engineer
District 4 - Richard N. Coffman, Maintenance Engineer District 5 - Robert MacNeil, Design Engineer District 6 - Richard Larson, Design and Planning Engineer WSDOT Library - Barbara Russo, Librarian

#### Transportation Research Council

Transportation Commission Vaughn Hubbard, Chair William J. Kamps\*# Richard Odabeshian\*

Jerry B. Overton Albert D. Rosellini Bernice Stern Leo B. Sweeney\*

\* Research Committee # Research Committee Chair

Federal Highway Administration

Paul C. Gregson, Division Administrator

filton "Bud" Egbers, President, Skagit Valley Trucking Richard Ford, Managing Partner, Preston, Thorgrimson, Ellis, Holman William Francis, Vice President, Burlington Northern R.R. Torn Gaetz, Project Manager, David Mowat & Company, Bellevue awrence Houk, Vice President, Lockheed Shipbuilding Charles H. Knight, President, Concrete Technology H. Carl Munson, VP for Strategic Planning, Boeing Co., Seattle Michael Murphy, President, Central Pre-Mix Concrete Richard Norman, President, Associated Sand & Gravel, Everett John Ostrowski, Public Works Director, Varncouver, WA Richard S. Page, President, Washington Roundtable James D. Ray, Senior Manager, IBM Company
Sudarshan Sathe, Director, Technical Services, Polycarb Inc., Cleveland, OH
Paul Turvill, General Manager, PACCAR, Technical Center, Mt. Vernon, WA

Gene L. Woodruff, Vice Provost for Research, UW Robert V. Smith, Associate Provost for Research, WSU Surinder K. Bhagat, Professor and Chair, Civil Engineering, WSU

Washington State Department of Transportation

Duane Berentson, Secretary A.D. Andreas, Deputy Secretary C.W. Beeman, District 5 Administrator R.E. Bockstruck, District 1 Administrator J.L. Clemen, Assistant Secretary for Mngt Services R.C. Cook, District 2 Administrate R.L. Daniels, Administrator, Public Affairs Office E.W. Ferguson, District 4 Administrator W. H. Hamilton, Assistant Secretary for Aeronautics W.I. Hordan, State Aid Engineer H. W. Parker, Assistant Secretary, Marine Transportation R.C. Schuster, Assistant Secretary for Highways J.H. Slakey, Manager, Public Transportation Office J.P. Toohey, Assistant Secretary for Ping, Res., and Pub. Trans. M.D. Tranum, District 6 Administrator D.J. Vandehey, State Construction Engineer A.T. Smelser, District 3 Administrator

Representative George Walk, Chair - Legislative Transportation Committee

Federal Highway Administration
M. Eldon Green, Region 10 Administrator

Otis C. Haselton, Region Office Research and T2 Engineer

Ernest J. Valach, Director, Regional Planning and Program Development

Paul C. Gregson, Division Administrator Barry Brecto, Division Office Programming and T2 Engineer Charles W. Chappell, Division Transportation Planner

Washington State Transportation Center (TRAC) (UW and WSU)

G. Scott Rutherford, Directo Ken Casavant, Associate Director, WSU Joe P. Mahoney, Associate Director, UW Khoserow Babasi, Senior Research Engineer Rhonda Brooks, Research Implementation Manager Mark Hallenbeck, Senior Research Engineer Ed McCormack, Research Engineer Army O'Brien, Coordinator Bev Odegaard, Budget Analyst Ron Porter, Word Processing Technician Cy Ulberg, Senior Research Engineer Cynthia Wallace, Clerk-Typist **Duane Wright, Research Aide** 

1. Report No.		TECHNICAL REPORT STANDARD TITLE
1. Report No.	2. Government Accession No.	3. Recipient's Catalog No.
WA-RD-129.1		· ·
4. Title and Subtitle		5. Report Date
ACQUISTIC CHARCTERISTI	CS OF ROADWAY SURFACES	September 10, 1987
MOODS TO CHARGIERTS T	OS OF NORDHALL SOM NOES	6. Performing Organization Code
7. Author(s)		8. Performing Organization Report No.
Professor James D. Ch	ialupnik <sub>.</sub>	
Donald S. Anderson		
9. Performing Organization Name and Sound and Vibration R		10. Work Unit No.
	cal Engineering, FU-10	6 - N
University of Washing		11. Contract or Grant No.
		Y2811, Task 35, Item #
Seattle, Washington 12. Sponsoring Agency Name and Add		13. Type of Report and Period Covered
		Final Report
	rtment of Transportation	
Transportation Buildi	3	14 5
Olympia, Washington	90004	14. Sponsoring Agency Code
This project studies on which they run age	the ways in which tire noise s and wears. Initial measur	changes as the pavement ements of the levels and
on which they run age spectral distribution have been made on a not concrete compositions way sections are undecompleted within six necessions.	the ways in which tire noise s and wears. Initial measur of noise generated at the tumber of road surfaces of a . In all, noise characteris r biannual study. All of the months of the initiation of essions are presented in gra	ements of the levels and ire-road surface interface variety of asphaltic and tics from thirty-one roadese sections were freshly the study. Data from the
on which they run age spectral distribution have been made on a not concrete compositions way sections are undecompleted within six necessity.	s and wears. Initial measur of noise generated at the tumber of road surfaces of a . In all, noise characteris r biannual study. All of the months of the initiation of	ements of the levels and ire-road surface interface variety of asphaltic and tics from thirty-one roadese sections were freshly the study. Data from the
on which they run age spectral distribution have been made on a not concrete compositions way sections are undecompleted within six necessions.	s and wears. Initial measur of noise generated at the tumber of road surfaces of a . In all, noise characteris r biannual study. All of the months of the initiation of	ements of the levels and ire-road surface interface variety of asphaltic and tics from thirty-one roadese sections were freshly the study. Data from the
on which they run age spectral distribution have been made on a not concrete compositions way sections are undecompleted within six necessions.	s and wears. Initial measur of noise generated at the tumber of road surfaces of a . In all, noise characteris r biannual study. All of the months of the initiation of	ements of the levels and ire-road surface interface variety of asphaltic and tics from thirty-one roadese sections were freshly the study. Data from the
on which they run age spectral distribution have been made on a not concrete compositions way sections are undecompleted within six necessions.	s and wears. Initial measur of noise generated at the tumber of road surfaces of a . In all, noise characteris r biannual study. All of the months of the initiation of	ements of the levels and ire-road surface interface variety of asphaltic and tics from thirty-one roadese sections were freshly the study. Data from the
on which they run age spectral distribution have been made on a not concrete compositions way sections are undecompleted within six necessions.	s and wears. Initial measur of noise generated at the tumber of road surfaces of a . In all, noise characteris r biannual study. All of the months of the initiation of	ements of the levels and ire-road surface interface variety of asphaltic and tics from thirty-one roadese sections were freshly the study. Data from the
on which they run age spectral distribution have been made on a not concrete compositions way sections are undecompleted within six necessions.	s and wears. Initial measur of noise generated at the tumber of road surfaces of a . In all, noise characteris r biannual study. All of the months of the initiation of	ements of the levels and ire-road surface interface variety of asphaltic and tics from thirty-one roadese sections were freshly the study. Data from the
on which they run age spectral distribution have been made on a not concrete compositions way sections are undecompleted within six necessions.	s and wears. Initial measur of noise generated at the tumber of road surfaces of a . In all, noise characteris r biannual study. All of the months of the initiation of	ements of the levels and ire-road surface interface variety of asphaltic and tics from thirty-one roadese sections were freshly the study. Data from the
on which they run age spectral distribution have been made on a not concrete compositions way sections are undecompleted within six necessions.	s and wears. Initial measur of noise generated at the tumber of road surfaces of a . In all, noise characteris r biannual study. All of the months of the initiation of	ements of the levels and ire-road surface interface variety of asphaltic and tics from thirty-one roadese sections were freshly the study. Data from the
on which they run age spectral distribution have been made on a not concrete compositions way sections are undecompleted within six necessity.	s and wears. Initial measur of noise generated at the tumber of road surfaces of a . In all, noise characteris r biannual study. All of the months of the initiation of	ements of the levels and ire-road surface interface variety of asphaltic and tics from thirty-one roadese sections were freshly the study. Data from the
on which they run age spectral distribution have been made on a not concrete compositions way sections are undecompleted within six necessions.	s and wears. Initial measur of noise generated at the tumber of road surfaces of a . In all, noise characteris r biannual study. All of the months of the initiation of	ements of the levels and ire-road surface interface variety of asphaltic and tics from thirty-one roadese sections were freshly the study. Data from the
on which they run age spectral distribution have been made on a nucleon concrete compositions way sections are undecompleted within six is	s and wears. Initial measur of noise generated at the tumber of road surfaces of a . In all, noise characteris r biannual study. All of the months of the initiation of	ements of the levels and ire-road surface interface variety of asphaltic and tics from thirty-one roadese sections were freshly the study. Data from the
on which they run age spectral distribution have been made on a national concrete compositions way sections are under completed within six of first four biannual sections.	s and wears. Initial measur of noise generated at the tumber of road surfaces of a . In all, noise characteris r biannual study. All of the months of the initiation of	ements of the levels and ire-road surface interface variety of asphaltic and tics from thirty-one roadese sections were freshly the study. Data from the phical form.
on which they run age spectral distribution have been made on a not concrete compositions way sections are undecompleted within six necessions.	s and wears. Initial measur of noise generated at the t umber of road surfaces of a . In all, noise characteris r biannual study. All of th months of the initiation of essions are presented in gra	ements of the levels and ire-road surface interface variety of asphaltic and tics from thirty-one roadese sections were freshly the study. Data from the phical form.
on which they run age spectral distribution have been made on a national concrete compositions way sections are under completed within six of first four biannual softies.  Tire Noise, Tire/Road	s and wears. Initial measur of noise generated at the t umber of road surfaces of a . In all, noise characteris r biannual study. All of th months of the initiation of essions are presented in gra	ements of the levels and ire-road surface interface variety of asphaltic and tics from thirty-one roadese sections were freshly the study. Data from the phical form.

# ACOUSTIC CHARACTERISTICS OF ROADWAY SURFACES

by James D. Chalupník Donald S. Anderson

Washington State Transportation Center

Department of Mechanical Engineering
University of Washington
Seattle, Washington

Final Report

Research Project Y-2811 Task 35 Item #623

Prepared for
Washington State Transportation Commission
Department of Transportation
and in cooperation with
U.S. Department of Transportation
Federal Highway Administration

September 10, 1987

The contents of this report reflect the views of the authors, who are responsible for the facts and the accuracy of the data presented herein. The contents do not necessarily reflect the official views or policies of the Washington State Department of Transportation or the Federal Highway Administration. This report does not constitute a standard, specification or regulation.

# TABLE OF CONTENTS

1.0	EXE	CUTIVE SUMMARY	1
2.0	BAC	KGROUND	1
о.е	OBJ	ECTIVE	а
4.0	PRO	CEDURE	а
	4.1	Literature Search	3
	4.2	Test vehicle selection	3
	4.3	Roadway test section identification	5
	4.4	Experimental equipment design	6
	4.5	Data acquisition	8
	4.6	Initial data collection	1 1
5.0	RES	ULTS	1 1
6.0	DIS	CUSSION	15
7.0	CON	CLUSIONS	16
8.0	LIS	T OF REFERENCES	17
APPE	ENDIX	A	21

	•

# LIST OF FIGURES

Figure	1	Tread	pri	nt of	tire	⊇ use	ed in	this	stu	ју	4	t
Figure	5	Schema	atic	draw	ing (	of th	e mic	roph	one :	locat	ion1	, <b>O</b>
Figure	3	Data f	for	Boein	g Fie	eld F	Refere	nce !	Sect:	ions	18	2
Figure	4	Data f	for	High	dens	ity F	CCP s	ecti	ons .		18	2
Figure	5	Data f	or	Latex	mod	ifiec	PCCF	sec	tions	s	13	3
Figure	6	Data f	for	Class	"D"	oper	grac	led Al	CP se	ectio	ns 1	3
Figure	7	Data f	or	Polye	ster	modi	fied	ACP 9	secti	ions	14	ŀ
Figure	8	Data f	or	Class	"B"	ACP	secti	ons			14	ŀ
Figure	9	Data f	or	Rubbe	r mod	difi∈	d ACF	sec	tions		15	5

#### ACOUSTIC CHARACTERISTICS OF ROADWAY SURFACES

# 1.0 EXECUTIVE SUMMARY:

This project is a pilot study of the way in which tire/road noise changes as the pavement ages and wears. Initial measurements of the noise levels and spectral distribution of noise generated at the tire-road surface interface have been made on number of road surfaces of a variety of asphaltic and concrete compositions. In all, noise characteristics are measured and analyzed biannually for forty-one roadway sections. All of these sections were freshly completed within six months of the initiation of the study. Data from the first four biannual sessions are presented in graphical form. At this point in this pilot study, the trends in the way the tire/road noise will change are not clearly established. Since the roadway sections are still in the early stages of their expected useful lives, even for the asphaltic sections, it was not expected that significant changes would show up during the pilot study.

## 2.0 BACKGROUND:

Measurement of the noise generated by the interaction between tires and the road surface are plentiful; the list of references gives selected references obtained from our literature search. Several of these are particularly useful in that they relate the near field measurement techniques used in this study to the far field noise levels, which can be thought of as the community noise exposure.

Information concerning the way in which noise produced by various payment types change with wear is lacking in the literature. In order to fill this information gap, the initial phase of this study (which will be referred to as "Phase I") was undertaken by WSDOT and the University of Washington. Since the main purpose of this investigation is to study the effects of wear and aging on the noise characteristics and normal life time expectancies for some roadway surfaces can reach as high as twenty years, the initial study, which is reported here, lasted only two years, can be considered to be a pilot study for the larger project.

The work performed in Phase I represents a major portion of the overall research project, because it involves setting up the experiment. This entails design of the experiment, design and fabrication of special hardware needed in the experiment, purchase of specialized equipment and instruments, selection of the test sections of roadway, setting of test and data protocols, etc.

An initial selection of over fifty roadway sections was ultimately reduced to thirty-one sections including several sections each of,

- · High density portland cement concrete.
- · Latex modified portland cement concrete.
- · Class "D" ACP Open Graded.
- · Polyester Fiber ACP.
- · Class "B" ACP.
- Rubber Mod ACP. (Plus ride asphalt)

The study is being performed jointly by Washington State Department of Transportation (WSDOT) and the Sound and Vibration Research Laboratory (SVRL) of the Department of Mechanical Engineering, University of Washington. Donald S. Anderson is the contact person for WSDOT, and Professor James D. Chalupník is the contact person for SVRL.

WSDOT is responsible for the data acquisition and SVRL is responsible for the experiment design and data analysis aspects of the project. SVRL has lead responsibility for preparation of reports, subject to WSDOT review.

# 3.0 OBJECTIVE:

The long term objective of this study is to measure the A-weighted levels and the spectra of tire noise from selected pavement types on a yearly basis to compare the effects of the following variables on tire noise:

- 1. Surface composition.
- 2. Surface wear.
- 3. Surface roughness.

# 4.0 PROCEDURE:

In order to accomplish the objective stated above it will be necessary to make measurements of the characteristics of noise generated by the tire interaction with a number of pavement types and to track their behavior over the lifetime of the surfaces. Before this could be done, certain preliminary tasks which set up the longer term experiment were required. These tasks were performed in the this phase of our study. Finally, the data acquisition portion of the study was initiated.

The tasks worked on in this phase of the overall project were:

- Literature search.
- Test vehicle selection.
- Roadway test section identification.
- Experimental equipment design.
- Data acquisition.
- Initial data collection. (four sessions)

These tasks are discussed in more detail in the following sections.

## 4.1 Literature Search

A literature search was performed at the University of Washington using the Computer-Based Reference Services, CBRS. This service provides access to a comprehensive cross-section of scientific holdings in libraries throughout the US and Western Europe. The library search, which included the topics pavement, surface, noise, and acoustic in several combinations, yielded 192 references, from which thirty-one references were selected for inclusion in the List of References at the end of this report. These references are given in alphabetical order by author.

#### 4.2 Test vehicle selection

Originally, it was planned that one of the Department of Transportation standard sedans would be used as the test vehicle for the road tests; however, further consideration dissuaded us from this plan. Since the tests ultimately will run for many years (10-20), it was not imagined that a sedan in the vehicle pool would be reliably available for that period of time. Furthermore, vehicle aging and tire wear would certainly lead to problems in controlling the variability of the test conditions. Researchers in Europe have used trailers for tire noise stidies for a number of years, so the advantages of this approach were investigated.

Advantages offered by using a trailer for this research are:

- 1) The trailer could be made available always.
- 2) The same tire(s) can be used for the entire study period.
- 3) The microphone can be moved further from the exhaust, motor, differential, and transmission and other noise sources in the propulsion system.
- 4) It is not necessary to mount and demount the microphone mounting bracket from the test vehicle after each test run, as would be required if a vehicle from the pool were to be used.

A utility trailer was purchased for \$630 for exclusive use on this project. The trailer is fitted with standard duty passenger tires. (Sears "Superguard" P185/75R14 radials) A tread print of the tire is shown in Figure 1. The trailer is strictly controlled and is used only for this project, so mileage on the tires is limited to about 500 miles per year. The trailer and tires should last the duration of the total project. The trailer has been loaded to a wheel load of 780 pounds to simulate the wheel load of a mid-sized sedan.




Figure 1 Tread print of the Sears Superguard radial tire used in this study.

In the first series of tests, a pickup truck from the Department of Mechanical Engineering at the University of Washington was used to pull the trailer, but this was not completely satisfactory, because the truck was old and under-powered. There was no guarantee that the truck would last the project out. As an alternative, a new V-8 powered van was located in the DOT vehicle pool. Thus far, we have been able to reserve this vehicle at the times that we are scheduled to make road tests.

# 4.3 Roadway test section identification

One of the first actions that needed to be performed before this study could be initiated was to identify the test sections that would be used for the remainder of the study period. Since our WSDOT representation is with District #1, it was logical to select test sections in that district. It is also the best solution logistically, since the University of Washington is located in District #1.

Don Anderson coordinated these efforts and created a list of over fifty potential test sections in District #1 ranging from the Skagit County line on the north to Olympia on the south and as far east as the Kittitas County line at Snoqualmie Summit. The principal criterion used for the selection process was that the candidate section be recently completed in the summer of 1985. Other criteria included the surface type (in order to provide a broad variety of road surface types) and ease of access to the test section from our center of operations at the University of Washington.

The large number of test sections was selected to provide a large enough sample to provide the necessary statistical confidence level. In particular, it has been noted that there is significant variability in the surface characteristics of a particular type of road serface from one installation to another, and in some cases, variability has been observed in a single paving job in which the stretch of roadway is layed down by the same contractor.

In the initial proposal, it was thought that only a few sections of highway would be used, and that these sections would be studied intensively. The availability of a number of newly completed sections of pavement in District #1 allowed us to extend the study to a larger number of test sections, which it is thought would give a better distribution of data for the study. The roadway types selected represent most of the surface preparations currently used by WSDOT. These include the following surfaces,

- · High density portland cement concrete.
- · Latex modified portland cement concrete.
- Class "D" ACP Open Graded.
- · Polyester Fiber ACP.
- · Class "B" ACP.
- Rubber Mod ACP. (Plus ride asphalt)

Most of the sections south of Tacoma are on bridges, which offered little difference from several other sections nearer the center of operation and, consequently, were abandoned. Another section, the Renton "S"-curves, was abandoned because the surface, which is an asphalt overlayment started lifting, making that section unsatisfactory for our measurements. Additionally, we were unable to consistently maintain our test speed of 55 MPH in that area due to congestion during normal test times.

After the narrowing process, we are left with 41 test sections, which, are listed in Table I below. The lanes are identified by a number and a direction. Lanes are numbered from the left most lane outward to the shoulder; whereas, the directions are abreviations of North Bound, East Bound, etc. Aerial photographs of the test sections are given in Appendix A.

Test sections 1 and 2 are of particular interest, because they are sections of a roadway that have been laid down for a relatively long period of time and are virtually unused; therefore, they represent surfaces that should remain relatively constant during the test period. By comparing the data from these sections from run to run, we can obtain a measure of how consistent our measurements are. These sections will be referred to as our "Reference sections" in future.

The reference sections are located on a service road on King County International Airport (Boeing Field). They were chosen because they are lightly used and long enough for us to get our vehicle up to the required speed of 55 mph. It would have been preferable for the reference sections to be portland cement concrete sections, but it is not common to lay down roadway sections of PCC that will not be used heavily.

The test sections all lie in the Puget Sound Basin and are within a couple hundred feet of sea level and within a 40 mile radius of the University of Washington , with the exception of sections 38-41, which are located at or near the summet of Snoqualmie Pass at an elevation of 3,022 feet. With this exception all of the test sections are exposed to the same climatic conditions.

## 4.4 Experimental equipment design

As in many experiments, a goodly portion of the time spent during the initial phase of this project was spent in selecting, designing and manufacturing the hardware to be used in the data gathering phase. Substantial time was saved by purchasing a test trailer, rather than trying to design hardware to fit on a DOT vehicle because of the simple geometry of the test trailer.

Table I
Compilation of Test Roadway Sections
Giving the Location, Lane and Pavement Type

No. 5.1	R. Description	Lane	Pavement
1.	King County Airport Reference Sec.	1 SB	Class "B" ACP
2.	King County Airport Reference Sec.	1 NB	Class "B" ACP
3. I-	5 Puyallup River to King Co. Line	2 SB	Class "D" ACP Open Graded
4. I-	5 Puyallup River to King Co. Line	1 NB	Class "D" ACP Open Graded
5. I-	·	3 SB	Latex ModifiedPCCP
6. I-	5 S.R. 167 Overcrossing	3 SB	Latex Modified PCCP
7. I-	5 Portland Ave. Overcrossing	3 SB	Latex Modified PCCP
8.	West Seattle Bridge	1 WB	High Density PCCP
9.	West Seattle Bridge	5 MB	High Density PCCP
10.	West Seattle Bridge	1 EB	High Density PCCP
11.	West Seattle Bridge	5 EB	High Density PCCP
12. I-	5 Galer/Lakeview Viaduct	2 NB	Latex Modified PCCP
13. I-	5 Galer/Lakeview Viaduct	2 SB	Latex Modified PCCP
14. I-	5 Galer/Lakeview Viaduct	3 SB	Latex Modified PCCP
15. I-	5 Ship Canal Bridge	1 NB	Latex Modified PCCP
16. I-	5 Ship Canal Bridge	2 NB	Latex Modified PCCP
17. I-	5 Ship Canal Bridge	2 SB	Latex Modified PCCP
18. I-	5 Ship Canal Bridge	3 SB	Latex Modified PCCP
19. I-	5 Swamp Creek Interchange North	1 NB	Class "B" ACP
20. I-	5 Swamp Creek Interchange North	2 NB	Class "B" ACP
21. I-	5 Swamp Creek Interchange North	1 SB	Class "B" ACP
22. I-	5 Swamp Creek Interchange North	2 SB	Class "B" ACP
23. I-	5 Union Slough Bridge	1 NB	Latex Modified PCCP
24. I-	5 Union Slough Brid <b>ge</b>	5 NB	Latex Modified PCCP
25. I-		1 SB	Latex Modified PCCP
26. I-	<del>-</del>	3 SB	Latex Modified PCCP
27. I-	<del>-</del>	1 SB	Latex Modified PCCP
28. I-	<u> </u>	3 SB	Latex Modified PCCP
29. I-	· · · · · · · · · · · · · · · · · · ·	1 SB	Latex Modified PCCP
30. I-	· · · · · · · · · · · · · · · · · · ·	3 SB	Latex Modified PCCP
31. 53		1 NB	Class "B" ACP
32. 53		1 SB	Class "B" ACP
<b>33.</b> 53		1 NB	Polyester Fiber ACP
34. 53		1 SB	Polyester Fiber ACP
	O Dahlgren Rd. to Skagit Co. Line	1 NB	
	O Dahlgren Rd. to Skagit Co. Line	1 SB	Rubber Mod ACP
	405 Factoria I/C to Sunset I/C	HOV	Class "B" ACP
	90 Asahel Curtis I/C to Snow Shed	1 EB	High Density PCCP
	90 Asahel Curtis I/C to Snow Shed	2 EB	High Density PCCP
	90 West Snoqualmie Summit Interchange	3 EB	High Density PCCP
41. I-	90 West Snoqualmie Summit Interchange	4 EB	High Density PCCP

The most crucial item that had to be designed and fabricated was a mounting bracket for the test microphone. This device has to accurately hold the microphone close to the tire-pavement interface.

It was decided to position the microphone 20 cm from the edge of the tire on a 45° angle from the road surface and in the vertical plane containing the axle. The microphone, a Brüel & Kjær Model 4134 is fitted with an nose cone and a wind screen to minimize aerodynamic noise. This particular location was chosen because it is close enough so that the predominant noises at that location are the noises from the tire and from the tire/road interface. Located this close to the tire/road interface reduces the effect of interfering noises from other adjacent noise sources. This location has been shown to be close enough to the source of interest to prevent interference from most vehicles in adjacent lanes.

The microphone is located in the wind stream around the tire near the road surface. As such, it is exposed to the noise generated at the tire/road interface and to aerodynamic wind noise. To minimize the latter, a Brüel & Kjær Model UA 0386 nose cone and a model UA 0237 wind screen were used. Brock tested the nose cone in an anechoic chamber on a rotating boom at speeds above and below the speeds at which our tests were run. His results show that the wind induced noise with this configuration were 10 dB or more below the noises measured by us in these tests, indication that this is not a factor in the noise data reported here. The noise data channel was monitored during the tests by earphone to assure that the data was tire noise, and to avoid the presenting data from extremely loud vehicles passing near the microphone.

The original design for the microphone bracket consisted of a tubular aluminum bracket welded to a mounting plate that attached to the spring shackle on the left wheel of the 4' x 6' utility trailer. In order to provide maximum rigidity, the bracket was designed to pass behind the wheel the shortest way. This resulted in the bracket passing very close to the road surface. The bracket functioned well during the first series of road tests; however, during the second test series, the new test van and trailer encountered a tilted slab of concrete roadway, which tossed the van up and the trailer down against the discontinuous roadway destroying the microphone bracket and microphone.

A new bracket was designed to provide more clearance, and at the same time provide adequate stiffness. The new bracket has been in use since the accident with no further difficulty. A diagram showing the schematic location of the microphone relative to the trailer tire is shown in Figure 2.

## 4.5 Data acquisition

Before attacking such a long term project as this, it is important to asses the method in which the data will be acquired and cataloged. For the purposes of this project, the data is collected on magnetic tape, which is labeled and saved for future reference. After each biannual data gathering session, the data

is reduced to 1/3 octave band data using a Hewlett-Packard Model 3561A Dynamic Signal Analyzer and an H-P 236 computer, on which the data is stored on magnetic disk media. Duplicate data is maintained to insure that the data available for future reference.

A significant portion of the effort reported in this report was devoted to the design of the computer program used to acquire the data from the data runs and record it on disk files. Each run on each surface is recorded in graphical form in the figures presented in Appendix A.

The data is presented in 1/3 octave format to show the frequency distribution of the near field noise from the tire/road interface. This information is summarized by an A-weighted noise level, shown both graphically and numerically at the right hand side of the graph.




Figure 2 Schematic drawing of the microphone location relative to the tire on the test trailer.

# 4.6 Initial data collection

The ultimate goal of this project is to study the way in which the acoustical characteristics of tire/road noises change with the wear and aging of the road surface. The research on this project will take place over a period of several years in order to obtain the desired data on the effects of wear of road surfaces on noise generation. The paving projects we are studying were completed shortly before the beginning of Phase I. Over fifty new sections of pavement that had been laid down in the immediate past were identified as potential test sections in the first selection process. Further screening has reduced the total number to approximately forty-one sections of roadway that will be tracked during the life of these sections in WSDOT District #1, in western Washington state.

Work during the first year was very heavy, being devoted to designing, fabricating, and installing the test instrumentation on a test vehicle, collecting of initial data on the test surfaces, and performing the search of the literature, nevertheless, data was gathered in four sessions spaced approximately semiannually over the two-year period. These data have been compiled in Appendix A at the end of this report. Detailed analysis of this data awaits the completion, or at least the continuation, of this research project.

## 5.0 RESULTS:

A summary of the data is presented in Figures 3 through 9 in which the A-weighted noise levels recorded for the numerous test sections is presented in comparitive form. The data is presented as follows: The reference surface data is presented in Figure 3, which is followed by the data from the following types of surfaces, respectively.

- · High density portland cement concrete.
- · Latex modified portland cement concrete.
- · Class "D" ACP Open Graded.
- · Polyester Fiber ACP.
- Class "B" ACP.
- Rubber Mod ACP. (Plus ride asphalt)

All the data for each type of surface is plotted on the same graph, regardless of the location of the test section, source of construction materials, paving contractor, or other factors which might affect the acoustical characteristics of the section. There are some outlying points, but on the whole, the data is quite consistent.




Figure 3 A-weighted SPL's for the Boeing Field Reference Sections measured over the two-year period of this study.




Figure 4 A-weighted SPL's for the high density PCCP sections measured over the two-year period of this study.




Figure 5 A-weighted SPL's for the latex modified PCCP sections measured over the two-year period of this study.




Figure 6 A-weighted SPL's for the Class "D" open graded ACP sections measured over the two-year period of this study.




Figure 7 A-weighted SPL's for the polyester modified ACP sections measured over the two-year period of this study.




Figure 8 A-weighted SPL's for the Class "B" ACP sections measured over the two-year period of this study.




Figure 9 A-weighted SPL's for the rubber modified ACP sections measured over the two-year period of this study.

# 6.0 DISCUSSION:

Although this is only a pilot study several observations can be made on the basis of the data in hand. First, it is obvious that asphalt concrete pavement is quieter than portland cement concrete pavement in the initial phases of life span of these surfaces. Secondly, it is possible to observe trends in the early stages of the roadway noise development. The asphalt pavements show a definite tendency to increase in A-weighted Sound Pressure Level with age over the short period observed here; whereas, noise levels for the portland cement concrete (modified or not) seem to remain relatively constant over this same period.

These observations are consistent with our common understanding of how these surfaces age and wear. The portland cement surfaces are more durable and have a longer expected lifetime; whereas, the asphaltic surfaces wear more rapidly exposing the coarse agregate more rapidly. The portland cement surfaces wear more slowly, and so the coarse agregate is not not yet exposed. On the other hand, the traction enhansing brush marks that were scribed into the surface have not worn as quickly as had been expected, and so the contribution of these marks to the noise has kept the noise level of this type of payement higher than expected.

# 7.0 CONCLUSIONS:

While this research project is only beginning, it is obvious that the project is proceeding at a steady pace and we have every right to expect that data not previously available in the literature will result from this study. The methodology for the study has been firmly defined and an excellent sample base for statistical analysis of the problem has been established.

# 8.0 LIST OF REFERENCES:

- 1. Agent, K.R. & Zegeer, C.V., "Effect of Pavement Texture on Traffic Noise (Abridgment)", Transportation Research Record N602 pp43-45, 1976, TRB Pubs Office, 2101 Constitution Ave, NW, Washington, D.C.
- 2. Andersson, O., "Vehicle Noise from Coarse Texture Pavements", National Swedish Road & Traffic Research Institute, Fack S-581 O1, Linkoeping, Sweden.
- 3. Anon., "Noise from the Interaction of Tire and Road", Kinkopings University, Sweeden, Nov 1982.
- 4. Bermann, M. "Noise Generation by Tire Vibrations", Noise Control Foundation, P.O.Box 1758, Poughkeepsie, NY, 12603, 1980.
- 5. Bond, R. et al., "Tyre/Road Surface Interaction", Highway Engineer, Vol 23, no 11, Nov, 1976, pp 11-20.
- 6. Brock, M., "Wind and Turbulence Noise of Turbulence Screen, Nose Cone and Sound Intensity Probe with Wind Screen", Technical Review, No.4, 1986, Brüel & Kjær Instruments, Inc., 185 Forest St., Marlborough, MA, 01752.
- 7. Franklin, R.E., et al., "Road Surfaces and Traffic Noise", Transport and Road Research Laboratory, Old Wokingham Rd., Crowthorne, RG11 6AU, Berkshire, England.
- 8. Kenton, E., "Highway Traffic Noise (A Bibliography with Abstracts)", National Technical Information Service, 5285 Port Royal Rd., Springfield, VA 22161.
- 9. Lawther, J.M., "Pavement Effects in Tire/Pavement Interaction Noise", Transportation Research Board, Pennsylvania State University, University Park, PA.
- 10. Leasu, W.A., Jr. et al., "Automobile Tire Noise: Results of a Pilot Study and Review of the Open Literature. Final Report", National Bureau of Standards, Washington, D.C., 20234, 1975. NTIS DOT-TST-76-4.
- 11. Leasure, W.A., "Truck Tire Noise Preliminary Results of a Field Measurement Program", Purdue University, West Lafayette, IN, 47906, 1971.

- 12. Leasure, W.A.J. & Corley, D.M., "Truck Noise I-B. Spectral and Directional Characteristics of Noise Generated by Truck Tires", National Bureau of Standards, Washington, D.C., 20234, 1974.
- 13. May, D.N. & Osman, M.M., "Noise from Retextured New Concrete and Asphalt Road Surfaces", Noise Control Foundation, P.O.Box 1758, Poughkeepsie, NY, 12603, 1978.
- 14. Mitrey, R.J. et al., "Effects of Selected Pavement Surface Textures on Tire Noise", New York State Department of Transportation, Engineering Research & Development Bur, 1220 Washington Ave., Albany, NY, 1975.
- 15. Nelson, P. M. & Ross, N. F., "Noise from Vehicles Running on Open Textured Road Surfaces", Transport and Road Research Laboratory, Old Wokingham Rd., Crowthorne, RG11 6AU, Berkshire, England.
- 16. O'Connor, J., "Traffic Noise; A Comparison of Traffic Noise Generated by Tire/Pavement Interaction on Six Different Surface Textures Applied to a Portland Cement Concrete Pavement and Three Different Bituminous Pavements", Minnesota Dept. of Transportation, 408 Transportation Bldg, John Ireland Boulevard, St. Paul, MN.
- 17. O'Connor, J.R., "Noise Generated by an Aggregation of Vehicles Interacting with Thirteen Different Road Surfaces", Noise Control Foundation, P.O.Box 1758, Poughkeepsie, NY, 12603, 1980.
- 18. Osman, M. M. & May, D. N., "Relative Influence of Pavement Texture and Tire Type on Pavement/Tire Noise", SAE 800282, Society of Automotive Engineers, 1982.
- 19. Reiter, S.F.J., et al., "Truck Noise VII-A. Experimental Investigation of Truck Tire Sound and Vibration", North Carolina State University, Department of Mechanical and Aerospace Engineering, Raleigh, NC 20590, 1974.
- 20. Salt, G.F., "Skid-Resistant Road Surfacings and Tyre Noise", Institution of Civil Engineers, Porceedings Vol. 66, Feb 1979, pp 115-125.

- 21. Samuels, S.E., "An Investigation of the Effects of Road Surface Macrotexture on Roadside Noise", Australian Road Research Board, 500 Burwood Rd., Vermont, South Victoria, 3133, Australia.
- 22. Sandberg, U. & Descornet, G., "Description of Methodology Concerning the Identification of Two Generation Mechanisms for Tire/Road Noise and the Differentiation of the Noise into the Two Mechanisms", National Swedish Road & Traffic Research Institute, and the Belgian Road Research Center, VTI. Meddelanden, N325A, 1982.
- 23. Sandberg, U. & Descornet, G., "Road Surface Influence on Tire/Road Noise -- 1", Noise Control Foundation, P.O.Box 1758, Poughkeepsie, NY, 12603, 1980.
- 24. Sandberg, U., "First Proposal for Two Standard Surfaces for Measurement of External Tyre/Road Noise", National Swedish Road & Traffic Research Institute, Fack S-581 01, Linkoeping, Sweden.
- 25. Sandberg, U., "Road Surface for Reduction of Tire Noise Emission", National Swedish Road & Traffic Research Institute, Fack S-581 O1, Linkoeping, Sweden.
- 26. Sandberg, U., "Toad Texture Induced External Tire Noise. Empirical Frequency Response Function for Tires", National Swedish Road & Traffic Research Institute, Fack S-581 01, Linkoeping, Sweden.
- 27. Sandberg, U. & Ejsmont, J.A., "Development of Three Methods for Measurement of Tire/Road Noise Emission: Coast-By, Trailer and Laboratory Drum", Noise Control Engineering Journal, Vol 27, No 3, Nov-Dec 1986.
- 28. Veres, R.E., "A Tire Noise Investigation and Test Method", SAE, 400 Commonwealth Dr. Warrendale, PA, 15096.
- 29. Veres, R.E., et al., "Use of Tire Noise as a Measure of Pavement Macrotexture", ASTM, 1916 Race St., Philadelphia, PA, 19103.
- 30. Walker, J.C. et al., "Noise Generated at the Tyre-Road Interface", John Wiley and Sons, Inc., 605 Third Ave, New York, NY, 10016.

- 31. Williams, W.L., et al., "Noise Produced by Open-Graded Asphaltic Friction Courses", <u>Public Roads</u>, Vol 39, No 1, June 1975, pp16-20.
- 32. Kay, R.A. & Stephens, J.K., "Porous Friction Courses & Roadway Surface Noise", U.S.DOT, FHWA Implementation Div., Offices of R&D, Washington, E.C.20590.
- 33. Slutsky, S., et al., "Tire-Pavement Noise Measurement Using Transfer Functions", <u>Transportation Research Record 1033</u>, Transportation Research Board, National Research Council.
- 34. Liedl, W. & Köhler, E., "Tire Rolling Noise in Dry and Wet Conditions on Pavement Surfaces of Different Skid Resistance", <u>ASTM Special Technical Publication 793</u>, ASTM 1916 Race St., Philadelphia, PA, 19103.
- 35. Walker, J.C., "Tire/Road Interaction Studies to Reduce Noise and Improve Wet Grip", ASTM Special Technical Publication 773, ASTM 1916 Race St., Philadelphia, PA, 19103.

# APPENDIX A Aerial Views of Test Sections

Table A.1 Information About Sites in Photographs


				Construction	
Figure	Site		Lane	Completion	
o N	Š	Descriptions	o Z	Date	Pavement Surface Type
	_	Calibration Site - King County Airport (Reference Section)	SB	9 - 85	Class "B" ACP
	2	Calibration Site - King County Airport (Reference Section)	S Z	9 - 85	Class "B" ACP
2	က	I-5: Puyallup R. Bridge to King Co. Line	25B	6 - 85	Class "D" ACP Open Graded
	4	I-5: Puyallup R. Bridge to King Co. Line	<u>N</u>	6 - 85	Class "D" ACP Open Graded
က	2	1-5: Portland Ave., SR 167, E. "T" St. Overcrossings	3SB	1985	Latex Modified PCCP
	9	I-5: Portland Ave., SR 167, E. "T" St. Overcrossings	3SB	1985	Latex Modified PCCP
	7	1-5: Portland Ave., SR 167, E. "T" St. Overcrossings	3SB	1985	Latex Modified PCCP
4	∞	West Seattle Bridge	IWB	11 - 83	High Density PCCP
,	6	West Seattle Bridge	2WB	11 - 83	High Density PCCP
	0	West Seattle Bridge	IEB	7 - 84	High Density PCCP
	=	West Seattle Bridge	2EB	7 - 84	High Density PCCP
2	13	1-5: Galer - Lakeview Viaduct	2NB	1984	Latex Modified PCCP
	<u>8</u>	I-5: Galer - Lakeview Viaduct	2SB	1985	Latex Modified PCCP
	14	1-5: Galer - Lakeview Viaduct	3SB	1985	Latex Modified PCCP
9	15	I-5: Ship Canal Bridge	E N N	1984	Latex Modified PCCP
	91	I-5: Ship Canal Bridge	2NB	1984	Latex Modified PCCP
	17	I-5: Ship Canal Bridge	2SB	1985	Latex Modified PCCP
	8	I-5: Ship Canal Bridge	3SB	1985	Latex Modified PCCP

<u>Table A.l</u>, continued Information About Sites in Photographs

				Construction	
Figure	Site		Lane	Completion	
Š	No	Descriptions	N	Date	Pavement Surface Type
7	61	I-5: Swamp Creek Interchange North	<u>8</u>	98 - 9	Class "B" ACP
	20	I-5: Swamp Creek Interchange North	2NB	98 - 9	Class "B" ACP
	12	I-5: Swamp Creek Interchange North	1SB	98 - 9	Class "B" ACP
	22	I-5: Swamp Creek Interchange North	2SB	98 - 9	Class "B" ACP
œ	23	I-5: Union, Steamboat, Ebey Sloughs	N N	9 - 85	Latex Modified PCCP
	24	I-5: Union, Steamboat, Ebey Sloughs	2NB	9 - 85	Latex Modified PCCP
	25	1-5: Union, Steamboat, Ebey Sloughs	ISB	9 - 85	Latex Modified PCCP
	26	I-5: Union, Steamboat, Ebey Sloughs	3SB	9 - 85	Latex Modified PCCP
	27	I-5: Union, Steamboat, Ebey Sloughs	1SB	9 - 85	Latex Modified PCCP
	28	1-5: Union, Steamboat, Ebey Sloughs	3SB	9 - 85	Latex Modified PCCP
	29	I-5: Union, Steamboat, Ebey Sloughs	ISB	9 - 85	Latex Modified PCCP
	30	I-5: Union, Steamboat, Ebey Sloughs	3SB	9 - 85	Latex Modified PCCP
6	31	SR 530: Skagit Co. Line to Dahlgren Rd.	<u>R</u>	1985	Class "B" ACP
	32	SR 530: Skagit Co. Line to Dahlgren Rd.	ISB	1985	Class "B" ACP
	33	SR 530: Skagit Co. Line to Dahlgren Rd.	<u>8</u>	1985	Polyester Fiber ACP
	34	SR 530: Skagit Co. Line to Dahlgren Rd.	ISB	1985	Polyester Fiber ACP
	35	SR 530: Skagit Co. Line to Dahlgren Rd.	<u>R</u>	1985	Rubber Mod. ACP (PlusRide)
	36	SR 530: Skagit Co. Line to Dahlgren Rd.	ISB	1985	Rubber Mod. ACP (PlusRide)

Table A.l. continued Information About Sites in Photographs

		Pavement Surface Type		Class "B" ACP	PCCP	PCCP	PCCP	PCCP
Construction	Completion	Date	ž	9 - 85	9861	9861	9861	9861
	Lane	Š		HOV	IEB	2EB	3EB	4EB
		Descriptions		1-405: Factoria I/C to Sunset I/C HOV	1-90: Asahel Curtis I/C to Snowshed	1-90: Asahel Curtis I/C to Snowshed	1-90: West Summit Interchange	I-90: East Summit Interchange
	Site	No.		37	38	39	40	41
	Figure Site	No.		0	11, 12	,	13, 14	į



Location:

Calibration Site — King County Airport

County:

Scale:

King


1" = 500'

M.P. None

Date of Photography: 8-14-85

Figure

1



Scale:


I-5: Puyallup R. Bridge to King Co. Line

County: Pierce

1" = 1000'

M.P. 135.53 to 139.50

Date of Photography: 4-27-87




I-5: Portland Ave., SR 167, E.T St. Overcrossings

County:

Pierce

M.P. 134.85 to 135.22

Scale: 1'' = 500' Date of Photography: 6-17-87



West Seattle Bridge

County:

King

Scale: 1'' = 1000'

M.P. None

Date of Photography:

Figure


8-14-85



Location: I-5: Galer-Lakeview Viaduct

County: King M.P. 166.35 to 167.75

Scale: 1'' = 1000' Date of Photography: 8-14-85




Location: I-5: Ship Canal Bridge

County: King Scale: 1'' = 1000'

M.P. 168.06 to 169.20

Date of Photography: 8-14-85



I-5: Swamp Creek Interchange North


County:

Snohomish

Scale: 1'' = 1000'

M.P. 181.51 to 183.96

Date of Photography: 8-14-85




I-5: Union, Steamboat, Ebey Sloughs

Snohomish M.P. County:

Scale: 1" = 1000' 197.08 to 198.90

Date of Photography: 8-14-85 Figure


٤



Location: SR 530: Skagit Co. Line to Dahlgren Rd.

County: Snohomish M.P. 3.37 to 5.10

Scale: 1'' = 1000' Date of Photography: 6-18-82



I-405: Factoria I/C to Sunset I/C HOV

County:


Scale:

King

1" = 2000'

M.P. 4.54 to 10.53

Date of Photography: 8-14-85



I-90: Asahel Curtis I/C to Snowshed


King

County: Ning
- 1. 1" = 500'

M.P.46.95 to 54.94

Date of Photography: 11-14-85

Figure 11



I-90: Asahel Curtis I/C to Snowshed

County:


King

Scale: 1'' = 500'

M.P. 46.95 to 54.94

Date of Photography: 11-14-85

Figure




I-90: West Summit Interchange

County: King Scale: 1" = 500' ....

M.P. 46.95 to 54.94

Date of Photography: 11-14-85



I-90: East Summit Interchange

County: Kittitas Scale: 1'' = 500'

M.P. 46.95 to 54.94

Date of Photography: 11-14-85

•			
		•	